(79)

भारत सरकार/GOVERNMENT OF INDIA
रेल मंत्रालय/MINISTRY OF RAILWAYS
रेलवे बोर्ड (RAILWAY BOARD)

No. 2018/Sig/LX/2 **New Delhi, Dated :04.08.2025**

PCSTEs
All Zonal Railways.

Sub: Regarding LC Gates working.

During a recent incidence at a traffic level crossing gate, it was observed that the slot from the level crossing gate is immediately transmitted to the station master with the closure of the gate, with no provision of putting back the signal at 'ON' in case of emergencies.

2. In view of above, the following needs to be ensured:-

i. Provision of facility for gateman to put back the signal (protecting the gate) to ON as per IRSEM Para 14.1.10(b)(v).
ii. The extension of slot from gateman to station should be a deliberate action by gateman after ensuring the closing and locking of the gate and it being free of any obstruction.
iii. It should be ensured that the working of LC Gate is commensurate with the provisions in the SWR/GWR.

3. Zonal Railways are requested to work out an Action Plan to ensure implementation of the above in a time-bound manner under advice to this office.

Digitally signed by
RAMESHWER MEENA
Date: 04-08-2025
18:57:32

(रामेश्वर मीना)
(Rameshwer Meena)
कार्यकारी निदेशक(सिगनल)
Executive Director (Signal)
edsignal@rb.railnet.gov.in